

PROPOSAL

TO: Board of Commissioners, Union County, Ohio
 PROJECT: UNI-CR78A-001 BRIDGE REHABILITATION
 NAME: _____

The undersigned, having full knowledge of the site(s) of the Project, the specifications applicable to the Project, and the conditions of this Proposal hereby agrees to furnish all services, labor, materials and equipment necessary to complete the Project in accordance with the Plans and Detailed Specifications, within the time specified for completion and to accept payment in accordance with the unit prices stated below as full compensation for all furnished services, labor, material & equipment.

REF#	ITEM	ITEM EXT.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
ROADWAY							
1	201	11000	CLEARING AND GRUBBING	1	LUMP		\$0.00
2	202	42000	ANCHOR ASSY REMOVED, TYPE A	1	EACH		\$0.00
3	202	38001	GUARDRAIL REMOVED, AS PER PLAN	725.0	FT		\$0.00
4	203	10001	EXCAVATION, AS PER PLAN	91	CU YD		\$0.00
5	203	20000	EMBANKMENT	110	CU YD		\$0.00
6	204	10000	SUBGRADE COMPACTION	319	SQ YD		\$0.00
7	204	45000	PROOF ROLLING	1	HOUR		\$0.00
8	606	15050	GUARDRAIL, TYPE MGS	700	FT		\$0.00
9	606	26050	ANCHOR ASSEMBLY, MGS TYPE B	1	EACH		\$0.00
10	606	35003	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1, AS PER PLAN	4	EACH		\$0.00
11	254	01000	PAVEMENT PLANING, ASPHALT CONCRETE, 1.25"	534	SQ YD		\$0.00
12	254	01000	PAVEMENT PLANING, ASPHALT CONCRETE, 2"	267	SQ YD		\$0.00
13	254	01000	PAVEMENT PLANING, ASPHALT CONCRETE, 4"	110	SQ YD		\$0.00
EROSION CONTROL							
14	659	00530	SEEDING AND MULCHING, CLASS 3B	1300	SQ YD		\$0.00
15	659	20000	COMMERCIAL FERTILIZER	0.18	TON		\$0.00
15a	832	30001	EROSION CONTROL, AS PER PLAN	3500	EACH	\$1.00	\$3,500.00
16	659	35000	WATER	7	MGAL		\$0.00
17	670	00520	SLOPE EROSION PROTECTION MAT, TYPE B	400	SQ YD		\$0.00
PAVEMENT							
18	301	46000	ASPHALT CONCRETE BASE, PG64-22	22	CU YD		\$0.00
19	304	20000	AGGREGATE BASE	74	CU YD		\$0.00
20	407	10000	TACK COAT	110	GAL		\$0.00
21	441	10000	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	39	CU YD		\$0.00
22	441	50300	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)	9	CU YD		\$0.00
23	441	50000	ASPHALT CONCRETE LEVELING COURSE, TYPE 1, (448)	9	CU YD		\$0.00
TRAFFIC CONTROL							
24	626	00110	BARRIER REFLECTOR, TYPE 2, BIDIRECTIONAL	18	EACH		\$0.00
25	630	86010	GROUND MOUNTED SUPPORT, NO. 3 POST	9	FT		\$0.00
26	646	00490	STOP LINE	20	FT		\$0.00
27	630	86010	REMOVAL OF GROUND MOUNTED SIGN POST AND REERECTION	9	EACH		\$0.00
28	646	00094	EDGE LINE, 6"	0.28	MILE		\$0.00
29	646	00290	CENTER LINE	0.18	MILE		\$0.00

STRUCTURES (20' AND OVER)						
30	202	11201	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN	1	LUMP	\$0.00
30a	202	22900	APPROACH SLAB REMOVED	99	SQ YD	\$0.00
31	202	23500	WEARING COURSE REMOVED	610	SQ YD	\$0.00
32	503	21300	UNCLASSIFIED EXCAVATION	1	LUMP	\$0.00
33	509	10000	EPOXY COATED REINFORCING STEEL	17643	LB	\$0.00
34	510	10000	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT	194	EACH	\$0.00
35	511	21520	CLASS QC2 CONCRETE, SUPERSTRUCTURE	102	CU YD	\$0.00
36	519	11101	PATCHING CONCRETE STRUCTURE, AS PER PLAN	100	SQ FT	\$0.00
37	511	45710	CLASS QC1 CONCRETE, ABUTMENT	8	CU YD	\$0.00
38	512	10100	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	95	SQ YD	\$0.00
39	512	33010	TYPE 2 WATERPROOFING	4	SQ YD	\$0.00
40	515	12050	PRESTRESSED CONCRETE COMPOSITE BOX BEAM BRIDGE MEMBERS, LEVEL 1, CB21-48(55'-2)	21	EACH	\$0.00
41	518	22300	SPECIAL-STEEL DRIP STRIP	407	FT	\$0.00
41a	516	13600	1" PREFORMED EXPANSION JOINT FILLER	36	SQ FT	\$0.00
42	516	13901	2" PREFORMED EXPANSION JOINT FILLER, AS PER PLAN	84	SQ FT	\$0.00
43	516	31011	3" DEEP JOINT SEALER, AS PER PLAN	56	FT	\$0.00
44	516	41100	1/8" PREFORMED BEARING PAD	42	EACH	\$0.00
45	516	43200	ELASTOMERIC BEARING WITH INTERNAL LAMINATES ONLY (NEOPRENE) (10"x10"x2.4238" THICK)	84	EACH	\$0.00
46	517	70000	RAILING (TWIN STEEL TUBE)	339.83	FT	\$0.00
47	518	21200	POROUS BACKFILL WITH GEOTEXTILE FABRIC	14	CU YD	\$0.00
48	518	40000	6" PERFORATED CORRUGATED PLASTIC PIPE (PCPP)	80	FT	\$0.00
49	518	40010	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS (NPCPP)	40	FT	\$0.00
50	526	10001	REINFORCED CONCRETE APPROACH SLABS, APP (T=12")	47	SQ YD	\$0.00
51	526	15001	REINFORCED CONCRETE APPROACH SLABS, APP (T=13")	67	SQ YD	\$0.00
51a	509	20001	REINFORCING STEEL, REPLACEMENT OF EXISTING REINFORCING STEEL, AS PER PLAN	400	LB	\$0.00
MAINTENANCE OF TRAFFIC						
52	614	12420	DETOUR SIGNING	1	LUMP	\$0.00
53	614	11110	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASST.	40	HOUR	\$0.00
54	614	11000	MAINTAINING TRAFFIC	1	LUMP	\$0.00
55	619	16010	FIELD OFFICE, TYPE B	3	MNTH	\$0.00
56	623	10000	CONSTRUCTION LAYOUT STAKES AND SURVEYING	1	LUMP	\$0.00
57	624	10000	MOBILIZATION	1	LUMP	\$0.00
MISCELLANEOUS						
58	SPECIAL		PERFORMANCE AND PAYMENT BOND	1	LUMP	\$0.00
GRAND TOTAL						\$3,500.00